



ESTIMATE

Tidewater Home Improvement LLC
Class B Contractor #2705172863
414 Worster Ave
Hampton, Virginia 23669
United States

(757) 551-6413
tidehomepro.com

BILL TO

Chris Conley
Chris Conley
1406 Antoinette Cir
Hampton, VA 23663
United States

(757) 951-7924
skinscmc05@yahoo.com

Estimate Number: 1428
Estimate Date: September 30, 2026
Valid Until: October 7, 2026

Grand Total (USD): \$1,801.00

Framing & Carpentry	1
Sister 16 LF of 2x4 wall studs (4 studs @ 4 ft); replace 9.5 LF of window sill/plate framing (bottom plate @ 3.5 ft + 2 jack studs @ 3 ft); cut out and install an 18 SF section of 3/4 in. exterior plywood subfloor with blocking.	
Insulation	1
Install 24 SF of R-13 kraft-faced fiberglass insulation in the wall cavities behind the sink and window.	
Drywall & Paint	1
Hang, tape, mud, sand and prime 27 SF of mold-resistant greenboard on the lower wall beneath the window and cutouts; prep, caulk and touch up paint on the 3.5 LF window apron trim.	
Debris & Disposal	1
Haul away damaged lumber, subfloor, drywall scraps and jobsite waste.	

Grand Total (USD): **\$1,801.00**

Notes / Terms

SCOPE OF WORK

Framing & Carpentry: sister 16 LF of 2x4 wall studs (4 studs); replace 9.5 LF of window sill/plate framing (bottom plate + 2 jack studs); cut out and install an 18 SF section of 3/4 in. exterior plywood subfloor with blocking.

Insulation: install 24 SF of R-13 kraft-faced fiberglass insulation in the wall cavities behind the sink and window.

Drywall & Paint: hang, tape, mud, sand and prime 27 SF of mold-resistant greenboard; prep, caulk and touch up paint on the 3.5 LF window apron trim.

Debris & Disposal: haul away damaged lumber, subfloor, drywall scraps and jobsite waste.

NOT INCLUDED: cabinet or countertop removal and reinstallation; flooring installation; painting of the full room; mold or fungus treatment; permits.

Notes:

**Jobsite will be left clean once completed.



**Contractor is not responsible for damage caused inside the home while repairing.

Warranty:

**12 months workmanship on the project.

Payment Terms:

Total Project Cost: \$1,801.00

Deposit to Schedule: \$900.50

Final Payment: \$900.50

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: valid until 10/07/2026.